

STANDARDS

a BICSI International Standard

ANSI/BICSI 002-2019

**Data Center
Design and Implementation
Best Practices**



ANSI/BICSI 002-2019

Data Center Design and Implementation Best Practices

Committee Approval: January 21, 2019

ANSI Final Action: February 8, 2019

First Published: May 1, 2019



BICSI International Standards

BICSI international standards contain information deemed to be of technical value to the industry and are published at the request of the originating committee. The BICSI International Standards Program subjects all of its draft standards to a rigorous public review and comment resolution process, which is a part of the full development and approval process for any BICSI international standard.

The BICSI International Standards Program reviews its standards at regular intervals. By the end of the fifth year after a standard's publication, the standard will be reaffirmed, rescinded, or revised according to the submitted updates and comments from all interested parties.

Suggestions for revision should be directed to the BICSI International Standards Program, care of BICSI.

Copyright

This BICSI document is a standard and is copyright protected. Except as permitted under the applicable laws of the user's country, neither this BICSI standard nor any extract from it may be reproduced, stored in a retrieval system or transmitted in any form or by any means, electronic, photocopying, recording, or otherwise, without prior written permission from BICSI being secured.

Requests for permission to reproduce this document should be addressed to BICSI.

Reproduction may be subject to royalty payments or a licensing agreement.

Violators may be prosecuted.

Published by:



BICSI
8610 Hidden River Parkway
Tampa, FL 33637-1000 USA

Copyright © 2019 BICSI
All rights reserved
Printed in U.S.A.

Notice of Disclaimer and Limitation of Liability

BICSI standards and publications are designed to serve the public interest by offering information communication and technology systems design guidelines and best practices. Existence of such standards and publications shall not in any respect preclude any member or nonmember of BICSI from manufacturing or selling products not conforming to such standards and publications, nor shall the existence of such standards and publications preclude their voluntary use, whether the standard is to be used either domestically or internationally.

By publication of this standard, BICSI takes no position respecting the validity of any patent rights or copyrights asserted in connection with any item mentioned in this standard. Additionally, BICSI does not assume any liability to any patent owner, nor does it assume any obligation whatever to parties adopting the standard or publication. Users of this standard are expressly advised that determination of any such patent rights or copyrights, and the risk of infringement of such rights, are entirely their own responsibility.

This standard does not purport to address all safety issues or applicable regulatory requirements associated with its use. It is the responsibility of the user of this standard to review any existing codes and other regulations recognized by the national, regional, local, and other recognized authorities having jurisdiction (AHJ) in conjunction with the use of this standard. Where differences occur, those items listed within the codes or regulations of the AHJ supersede any requirement or recommendation of this standard.

All warranties, express or implied, are disclaimed, including without limitation, any and all warranties concerning the accuracy of the contents, its fitness or appropriateness for a particular purpose or use, its merchantability and its non-infringement of any third-party's intellectual property rights. BICSI expressly disclaims any and all responsibilities for the accuracy of the contents and makes no representations or warranties regarding the content's compliance with any applicable statute, rule, or regulation.

BICSI shall not be liable for any and all damages, direct or indirect, arising from or relating to any use of the contents contained herein, including without limitation any and all indirect, special, incidental, or consequential damages (including damages for loss of business, loss of profits, litigation, or the like), whether based upon breach of contract, breach of warranty, tort (including negligence), product liability or otherwise, even if advised of the possibility of such damages. The foregoing negation of damages is a fundamental element of the use of the contents hereof, and these contents would not be published by BICSI without such limitations.

TABLE OF CONTENTS

| | |
|---|--------------|
| PREFACE | xxvii |
| 1 Introduction | 1 |
| 1.1 General | 1 |
| 1.2 Purpose | 1 |
| 1.2.1 Users Within IT | 1 |
| 1.2.2 Users Within Facilities Group | 1 |
| 1.2.3 Staff Outside IT and Facilities Groups | 2 |
| 1.3 Categories of Criteria | 2 |
| 2 Scope | 2 |
| 3 Required Standards and Documents | 3 |
| 4 Definitions, Acronyms, Abbreviations, and Units of Measurement | 7 |
| 4.1 Definitions | 7 |
| 4.2 Acronyms and Abbreviations | 25 |
| 4.3 Units of Measurement | 27 |
| 5 Site Selection | 29 |
| 5.1 Introduction | 29 |
| 5.2 Site Evaluation | 29 |
| 5.2.1 General Requirements | 29 |
| 5.2.2 General Recommendations | 29 |
| 5.2.3 Risk Assessment | 29 |
| 5.2.4 Cost Evaluation Recommendations | 30 |
| 5.2.5 Existing Facilities Requirements | 30 |
| 5.3 Natural Hazards | 31 |
| 5.3.1 Introduction | 31 |
| 5.3.2 General Requirements | 31 |
| 5.3.3 Seismic Activity | 31 |
| 5.3.4 Volcanic Activity | 31 |
| 5.3.5 Wildfire | 33 |
| 5.3.6 Flood Plains | 33 |
| 5.3.7 Wind | 34 |
| 5.4 Natural Environment | 34 |
| 5.4.1 Introduction | 34 |
| 5.4.2 Ground Stability | 34 |
| 5.4.3 Lightning | 35 |
| 5.4.4 Groundwater | 36 |
| 5.4.5 Air Quality | 36 |
| 5.4.6 Noise | 37 |
| 5.4.7 Other Topography and Natural Environment Recommendations | 37 |
| 5.5 Man-Made Hazards | 37 |
| 5.5.1 Introduction | 37 |
| 5.5.2 Recommended Separation Distances | 37 |
| 5.5.3 Other Recommendations | 37 |

| | | |
|------------|--|-----------|
| 5.6 | Site Access and Location | 39 |
| 5.6.1 | Public Road Access Recommendations..... | 39 |
| 5.6.2 | Adjacent Property..... | 40 |
| 5.6.3 | Proximity to Existing or Redundant Data Center..... | 40 |
| 5.6.4 | Security and Emergency Services..... | 40 |
| 5.6.5 | Proximity to Skilled Labor..... | 40 |
| 5.7 | Utility Services | 41 |
| 5.7.1 | Introduction..... | 41 |
| 5.7.2 | Power and Electrical Service..... | 41 |
| 5.7.3 | Communications..... | 44 |
| 5.7.4 | Water Service..... | 45 |
| 5.7.5 | Sanitary Sewer..... | 47 |
| 5.7.6 | Natural Gas and Other Fuels..... | 47 |
| 5.8 | Regulations (Local, Regional, Country) | 48 |
| 5.8.1 | Air Quality Requirements..... | 48 |
| 5.8.2 | Noise Requirements..... | 48 |
| 5.8.3 | Towers and Tall Structures Requirements..... | 48 |
| 5.8.4 | Fuel Tanks Requirements..... | 48 |
| 5.8.5 | Generator Requirements..... | 48 |
| 5.8.6 | Site Access and Required Parking..... | 48 |
| 5.8.7 | Setbacks and Sight Lines..... | 48 |
| 5.8.8 | Environmental Assessment..... | 48 |
| 6 | Space Planning | 49 |
| 6.1 | Overall Facility Capacity | 49 |
| 6.1.1 | General..... | 49 |
| 6.1.2 | Module and Modular Design..... | 49 |
| 6.2 | Power Systems | 50 |
| 6.2.1 | Introduction..... | 50 |
| 6.2.2 | Electric Utility Service Feeds..... | 56 |
| 6.2.3 | Generator Power..... | 56 |
| 6.3 | Cooling Capacity | 57 |
| 6.3.1 | Introduction..... | 57 |
| 6.3.2 | Recommendations..... | 58 |
| 6.3.3 | Additional Information..... | 59 |
| 6.4 | Data Center Supporting Spaces | 59 |
| 6.4.1 | Adjacencies of Functional Spaces..... | 59 |
| 6.4.2 | Security..... | 61 |
| 6.4.3 | Telecommunications Entrance Room..... | 62 |
| 6.4.4 | Command Center..... | 63 |
| 6.4.5 | Helpdesk..... | 63 |
| 6.4.6 | Print..... | 63 |
| 6.4.7 | Loading Dock..... | 63 |
| 6.4.8 | Storage..... | 64 |
| 6.4.9 | Engineering Offices..... | 64 |
| 6.4.10 | Administrative..... | 65 |
| 6.4.11 | Environmental Design..... | 65 |
| 6.4.12 | Waste/Recycle..... | 65 |
| 6.5 | Placement of Equipment When Using Access Floors | 65 |
| 6.5.1 | Cooling..... | 65 |
| 6.5.2 | Power Distribution..... | 66 |
| 6.5.3 | Fire Protection Systems..... | 67 |

| | | |
|------------|---|-----------|
| 6.6 | Computer Room | 67 |
| 6.6.1 | Introduction | 67 |
| 6.6.2 | Telecommunications Spaces and Areas..... | 68 |
| 6.6.3 | Equipment Racks and Frames | 68 |
| 6.6.4 | Computer Room Layout | 71 |
| 6.6.5 | Adjacencies and Other Space Considerations..... | 75 |
| 6.7 | Design for Performance | 77 |
| 6.7.1 | Introduction | 77 |
| 6.7.2 | Data Center Metrics..... | 78 |
| 6.7.3 | Scalability..... | 79 |
| 6.7.4 | Instrumentation and Control..... | 79 |
| 6.7.5 | Data Center Energy Saving Design Opportunities | 80 |
| 7 | Architectural | 81 |
| 7.1 | Facilities Planning | 81 |
| 7.1.1 | General Overview..... | 81 |
| 7.1.2 | Site Selection..... | 81 |
| 7.1.3 | Data Center Location Relative to Ground Level | 82 |
| 7.2 | General Design Concepts..... | 82 |
| 7.2.1 | Levels of Reliability | 82 |
| 7.2.2 | Facility Purpose | 82 |
| 7.2.3 | Multiusers Versus Single User Groups | 83 |
| 7.2.4 | Equipment Change Cycle | 83 |
| 7.2.5 | Occupied Versus Unoccupied Data Centers..... | 83 |
| 7.2.6 | Data Center Location Within Building..... | 83 |
| 7.2.7 | Type of Building..... | 84 |
| 7.2.8 | Multitenant Buildings..... | 84 |
| 7.2.9 | 24/7 Operation of Data Center..... | 84 |
| 7.2.10 | Temperature and Humidity Control..... | 84 |
| 7.2.11 | Materials..... | 84 |
| 7.3 | General Paths of Access | 85 |
| 7.3.1 | General Access | 85 |
| 7.3.2 | Data Center Access..... | 85 |
| 7.3.3 | Equipment Access | 85 |
| 7.3.4 | Telecommunications Access Provider Entry into Computer Rooms..... | 86 |
| 7.3.5 | Vendor Access..... | 86 |
| 7.3.6 | Support Equipment Service Access..... | 86 |
| 7.4 | Planning Detail | 86 |
| 7.4.1 | Entry | 86 |
| 7.4.2 | Command Center and Personnel Areas | 86 |
| 7.4.3 | Printer Room | 87 |
| 7.4.4 | Media Storage Room | 87 |
| 7.4.5 | Restrooms and Break Rooms..... | 87 |
| 7.4.6 | Computer Room | 87 |
| 7.4.7 | Entrance Rooms..... | 87 |
| 7.4.8 | Mechanical Equipment Space..... | 88 |
| 7.4.9 | Electrical Room and UPS Room | 88 |
| 7.4.10 | Battery Room..... | 88 |
| 7.4.11 | Fire Suppression Room | 89 |
| 7.4.12 | Circulation | 89 |
| 7.4.13 | Equipment Staging and Storage..... | 89 |
| 7.4.14 | Equipment Repair Room | 89 |

| | | |
|------------|---|------------|
| 7.5 | Construction Considerations | 89 |
| 7.5.1 | Structure Preparation | 89 |
| 7.5.2 | Floor Slab..... | 89 |
| 7.5.3 | Computer Room Envelope Wall Construction | 90 |
| 7.5.4 | Nonrated Partitions | 90 |
| 7.5.5 | Vapor/Moisture Seal | 90 |
| 7.5.6 | Door and Glazed Openings..... | 90 |
| 7.5.7 | Fire-Rated Construction..... | 91 |
| 7.5.8 | Access Control Systems..... | 91 |
| 7.5.9 | Airborne Particles | 92 |
| 7.5.10 | Access Flooring Systems | 92 |
| 7.5.11 | Ceilings | 95 |
| 7.5.12 | Equipment Bracing Systems | 96 |
| 7.5.13 | Computer Room Finishes | 96 |
| 7.5.14 | Roof Systems | 96 |
| 8 | Structural | 97 |
| 8.1 | Building Code Compliance and Coordination | 97 |
| 8.1.1 | Requirements | 97 |
| 8.1.2 | Additional Information | 97 |
| 8.2 | Impact of Site Location on Structural Loading | 97 |
| 8.2.1 | Introduction..... | 97 |
| 8.2.2 | Recommendations..... | 97 |
| 8.3 | Structural Concerns Specific to Data Center Design | 97 |
| 8.3.1 | Floor Load | 97 |
| 8.3.2 | Raised Access Floors | 98 |
| 8.3.3 | Mission Critical Equipment in Seismically Active Areas..... | 98 |
| 8.3.4 | Wind | 99 |
| 8.3.5 | Earthquake | 99 |
| 8.3.6 | Blast and Terrorist Attack..... | 100 |
| 8.3.7 | Ice Shard Impact | 100 |
| 9 | Electrical Systems | 101 |
| 9.1 | Overview | 101 |
| 9.1.1 | Introduction..... | 101 |
| 9.1.2 | Requirements | 101 |
| 9.1.3 | Availability and Uptime..... | 101 |
| 9.1.4 | Redundancy | 102 |
| 9.1.5 | Capacity Versus Utilization Efficiency..... | 102 |
| 9.1.6 | Electrical Class Ratings | 104 |
| 9.2 | Utility Service | 118 |
| 9.2.1 | Utility Service Planning..... | 118 |
| 9.2.2 | Low-Voltage Utility Services | 119 |
| 9.2.3 | Medium-Voltage and High-Voltage Utility Services..... | 120 |
| 9.2.4 | Protective Relaying..... | 120 |
| 9.3 | Distribution | 120 |
| 9.3.1 | Requirements | 120 |
| 9.3.2 | UPS Rectifier or Motor Inputs..... | 121 |
| 9.3.3 | Static Switch Bypass Inputs..... | 121 |
| 9.3.4 | UPS System Bypass..... | 121 |
| 9.3.5 | Input Source Transfer | 121 |
| 9.3.6 | Generator Controls and Paralleling..... | 123 |
| 9.3.7 | Unit Substations..... | 124 |
| 9.3.8 | UPS Systems..... | 124 |
| 9.3.9 | UPS Output Distribution..... | 133 |

| | | |
|-------------|--|------------|
| 9.3.10 | Power Distribution Units (PDUs)..... | 134 |
| 9.3.11 | Automatic Static Transfer Switches | 137 |
| 9.3.12 | Power Strips..... | 137 |
| 9.3.13 | Direct Current (DC) Power Systems | 138 |
| 9.3.14 | Busway Power Distribution..... | 141 |
| 9.3.15 | Computer Room Equipment Power Distribution..... | 142 |
| 9.3.16 | Emergency Power Off (EPO) Systems..... | 153 |
| 9.3.17 | Fault Current Protection and Fault Discrimination..... | 155 |
| 9.4 | Mechanical Equipment Support..... | 155 |
| 9.4.1 | Introduction | 155 |
| 9.4.2 | Requirements..... | 157 |
| 9.4.3 | Recommendations | 157 |
| 9.5 | Uninterruptible Power Supply (UPS) Systems | 158 |
| 9.5.1 | Introduction | 158 |
| 9.5.2 | Sizing and Application | 159 |
| 9.5.3 | Technologies..... | 161 |
| 9.5.4 | Paralleling and Controls | 163 |
| 9.5.5 | Batteries and Stored Energy Systems | 164 |
| 9.6 | Standby and Emergency Power Systems..... | 170 |
| 9.6.1 | Sizing and Application | 170 |
| 9.6.2 | Starting Systems | 172 |
| 9.6.3 | Fuel Systems..... | 172 |
| 9.6.4 | Fuel Tank and Piping..... | 173 |
| 9.6.5 | Exhaust Systems | 173 |
| 9.6.6 | Cooling Systems | 173 |
| 9.6.7 | Mounting | 174 |
| 9.7 | Automation and Control..... | 174 |
| 9.7.1 | Introduction | 174 |
| 9.7.2 | Monitoring..... | 174 |
| 9.7.3 | Control..... | 175 |
| 9.7.4 | System Integration..... | 175 |
| 9.8 | Lighting | 175 |
| 9.8.1 | Introduction | 175 |
| 9.8.2 | General Recommendations..... | 176 |
| 9.8.3 | Computer Rooms..... | 176 |
| 9.8.4 | Support Areas | 177 |
| 9.9 | Bonding, Grounding, Lightning Protection, and Surge Suppression | 177 |
| 9.9.1 | Introduction | 177 |
| 9.9.2 | General Recommendations..... | 182 |
| 9.9.3 | Lightning Protection..... | 183 |
| 9.9.4 | Surge Suppression/Surge Protective Devices (SPDs)..... | 183 |
| 9.9.5 | Telecommunications Surge Protection | 185 |
| 9.9.6 | Building Ground (Electrode) Ring | 186 |
| 9.9.7 | Supplementary Bonding and Grounding | 186 |
| 9.9.8 | Information Technology Equipment Interconnections | 192 |
| 9.9.9 | Power System Bonding and Grounding..... | 195 |
| 9.10 | Labeling and Signage | 200 |
| 9.10.1 | Introduction | 200 |
| 9.10.2 | Requirements | 200 |
| 9.10.3 | Recommendations | 201 |
| 9.11 | Testing and Quality Assurance | 202 |
| 9.11.1 | Requirements | 202 |
| 9.11.2 | Recommendations | 202 |

| | | |
|-------------|---|------------|
| 9.12 | Ongoing Operations | 202 |
| 9.12.1 | Recommendations..... | 202 |
| 9.13 | Electrical Systems Matrix | 202 |
| 10 | Mechanical Systems | 221 |
| 10.1 | Codes, References and Terminology | 221 |
| 10.1.1 | Code Compliance and Coordination | 221 |
| 10.1.2 | References..... | 221 |
| 10.1.3 | Terminology Differences Between Codes and Telecommunications Standards..... | 221 |
| 10.2 | Selection of Heat Rejection Systems..... | 222 |
| 10.2.1 | Temperature and Humidity Requirements..... | 222 |
| 10.2.2 | Equipment Heat Release and Airflow Specifications | 222 |
| 10.2.3 | Control of Airborne Contaminants (Gases and Particles)..... | 223 |
| 10.3 | Heat Rejection and Computer Room Cooling Technologies..... | 224 |
| 10.3.1 | Introduction..... | 224 |
| 10.3.2 | Requirements for All Heat Rejection and Cooling Systems | 224 |
| 10.3.3 | Recommendations for All Heat Rejection and Cooling Systems..... | 224 |
| 10.3.4 | Fluid Based Heat Rejection and Cooling Systems..... | 224 |
| 10.3.5 | Direct Expansion Cooling Systems..... | 234 |
| 10.3.6 | Air-Side Economizer Systems | 238 |
| 10.3.7 | Dual Coil Cooling Solution | 241 |
| 10.4 | Mechanical Class Ratings | 241 |
| 10.4.1 | Introduction..... | 241 |
| 10.4.2 | Class F0 and F1 Description | 241 |
| 10.4.3 | Class F2 Description..... | 243 |
| 10.4.4 | Class F3 Description..... | 245 |
| 10.4.5 | Class F4 Description..... | 247 |
| 10.4.6 | Chiller Piping and Valve Redundancy..... | 250 |
| 10.5 | Air Flow Management..... | 252 |
| 10.5.1 | General Considerations..... | 252 |
| 10.5.2 | Introduction to Air Flow Management | 252 |
| 10.5.3 | Hot Aisle/Cold Aisle Concept..... | 253 |
| 10.5.4 | Access Floor Air Distribution..... | 254 |
| 10.5.5 | Overhead Air Distribution | 255 |
| 10.5.6 | Row-Integrated Cooling..... | 255 |
| 10.5.7 | Equipment Layout..... | 256 |
| 10.5.8 | Supply Air Layout | 256 |
| 10.5.9 | Return Air Layout..... | 256 |
| 10.5.10 | Cable Management | 256 |
| 10.6 | Ventilation (Outside Air) | 256 |
| 10.6.1 | Computer Rooms | 257 |
| 10.6.2 | Battery Rooms | 257 |
| 10.7 | Other Design Considerations..... | 258 |
| 10.7.1 | Humidity Control..... | 258 |
| 10.7.2 | Maximum Altitude..... | 258 |
| 10.7.3 | Noise Levels | 258 |
| 10.7.4 | Supplemental Cooling..... | 258 |
| 10.8 | Mechanical Equipment (Design and Operation) Recommendations | 260 |
| 10.8.1 | General Recommendations | 260 |
| 10.8.2 | Computer Room Air Conditioning (CRAC) and Computer Room Air Handling (CRAH) Units | 260 |
| 10.8.3 | Chilled Water Systems..... | 260 |
| 10.8.4 | Chillers..... | 261 |
| 10.8.5 | Cooling Towers..... | 261 |
| 10.8.6 | Adiabatic Cooling and Humidification | 261 |

| | | |
|--------------|--|------------|
| 10.8.7 | Thermal Storage | 261 |
| 10.8.8 | Piping and Pumps | 262 |
| 10.8.9 | Leak Detection..... | 262 |
| 10.8.10 | Water Supplies and Drainage | 262 |
| 10.8.11 | Materials in Air Plenums | 263 |
| 11 | Fire Protection | 265 |
| 11.1 | Introduction | 265 |
| 11.2 | Basic Design Elements..... | 265 |
| 11.3 | General Requirements and Recommendations..... | 265 |
| 11.3.1 | Requirements | 265 |
| 11.3.2 | Recommendations | 266 |
| 11.4 | Walls, Floors, and Ceilings | 266 |
| 11.4.1 | Requirements | 266 |
| 11.5 | Aisle Containment | 266 |
| 11.5.1 | Introduction | 266 |
| 11.5.2 | Aisle Containment Construction and Materials | 267 |
| 11.5.3 | Detection Systems in Contained Spaces | 267 |
| 11.5.4 | Suppression Systems in Contained Spaces | 267 |
| 11.5.5 | Additional Information | 268 |
| 11.6 | Handheld Fire Extinguishers..... | 269 |
| 11.6.1 | Requirements | 269 |
| 11.6.2 | Recommendations | 269 |
| 11.7 | Fire Detection..... | 269 |
| 11.7.1 | Area Requirements | 269 |
| 11.7.2 | Detector Technology | 270 |
| 11.7.3 | Early Warning Detection Systems | 271 |
| 11.8 | Fire Suppression | 271 |
| 11.8.1 | Water Sprinkler Systems | 271 |
| 11.8.2 | Gaseous Fire Suppression..... | 273 |
| 11.8.3 | Oxygen Depletion Systems..... | 274 |
| 11.9 | Fire Alarm Systems | 275 |
| 11.9.1 | Introduction | 275 |
| 11.9.2 | Requirements | 276 |
| 11.9.3 | Additional Information | 276 |
| 11.10 | Labeling and Signage | 276 |
| 11.10.1 | Requirements | 276 |
| 11.10.2 | Recommendations | 276 |
| 11.11 | Testing and Quality Assurance | 276 |
| 11.11.1 | Requirements | 276 |
| 11.11.2 | Recommendations | 276 |
| 11.12 | Ongoing Operations | 276 |
| 11.12.1 | Requirements | 276 |
| 11.12.2 | Recommendations | 276 |

| | | |
|-------------|---|------------|
| 12 | Security | 277 |
| 12.1 | Introduction | 277 |
| 12.2 | Definitions | 278 |
| 12.3 | Data Center Security Plan | 279 |
| 12.3.1 | Introduction | 279 |
| 12.3.2 | Recommendations | 279 |
| 12.3.3 | Physical Security Plan | 280 |
| 12.3.4 | IT/Cyber Security Plan | 280 |
| 12.3.5 | Disaster Recovery Plan | 280 |
| 12.3.6 | Emergency and Other Required Plans | 280 |
| 12.4 | Design and the Data Center Security Plan | 281 |
| 12.4.1 | Introduction | 281 |
| 12.4.2 | General | 281 |
| 12.4.3 | Access Control | 281 |
| 12.4.4 | Signage and Display Policy and Procedures | 282 |
| 12.4.5 | Fire Prevention, Detection, and Suppression | 282 |
| 12.4.6 | Monitoring and Alarms Policy and Procedures | 282 |
| 12.4.7 | Material Control and Loss Prevention | 283 |
| 12.4.8 | Surveillance Policy and Procedure | 283 |
| 12.5 | Building Site Considerations | 283 |
| 12.5.1 | Introduction | 283 |
| 12.5.2 | General Recommendations | 283 |
| 12.5.3 | Lighting | 284 |
| 12.5.4 | Perimeter Fencing and Barriers | 284 |
| 12.5.5 | Automotive Threats and Concerns | 285 |
| 12.5.6 | Threat History | 286 |
| 12.5.7 | Natural Threats and Concerns | 286 |
| 12.5.8 | Chemical, Biological, Radiological, Nuclear, and Explosives | 286 |
| 12.5.9 | Medical Disasters and Epidemics | 287 |
| 12.5.10 | Crime Prevention Through Environment Design | 287 |
| 12.6 | Data Center Elements | 288 |
| 12.6.1 | Barriers | 288 |
| 12.6.2 | Lighting | 297 |
| 12.6.3 | Access Control | 298 |
| 12.6.4 | Alarms | 306 |
| 12.6.5 | Surveillance | 307 |
| 12.6.6 | Time Synchronization | 309 |
| 12.7 | Building Shell | 310 |
| 12.7.1 | General Recommendations | 310 |
| 12.7.2 | Doorways and Windows | 311 |
| 12.7.3 | Signage and Displays | 311 |
| 12.7.4 | Construction | 311 |
| 12.7.5 | Elevators | 311 |
| 12.7.6 | Emergency Exits | 312 |
| 12.7.7 | Utilities | 312 |
| 12.7.8 | Hazardous Material Storage | 312 |
| 12.8 | Computer Room and Critical Facility Areas Special Considerations | 312 |
| 12.8.1 | General | 312 |
| 12.8.2 | Construction | 313 |
| 12.8.3 | Eavesdropping | 313 |
| 12.8.4 | Media | 313 |
| 12.8.5 | Fire Prevention | 313 |
| 12.8.6 | Dust | 313 |

| | | |
|-------------|---|------------|
| 12.9 | Disaster Recovery Plan | 314 |
| 12.9.1 | Introduction | 314 |
| 12.9.2 | Requirements | 314 |
| 12.9.3 | Recommendations | 314 |
| 12.9.4 | Security Plan and Disaster Recovery | 316 |
| 13 | Facility, Ancillary and IP-enabled Systems | 317 |
| 13.1 | Introduction | 317 |
| 13.2 | General Requirements | 317 |
| 13.2.1 | Spaces | 317 |
| 13.2.2 | Cabling and Cabling Infrastructure | 317 |
| 13.2.3 | Enclosures..... | 317 |
| 13.3 | General Recommendations..... | 317 |
| 13.4 | Data Center Infrastructure Management | 317 |
| 13.4.1 | Introduction | 317 |
| 13.4.2 | Recommendations | 318 |
| 13.5 | Facility Systems | 319 |
| 13.5.1 | Introduction | 319 |
| 13.5.2 | General Requirements | 319 |
| 13.5.3 | Building Automation and Management Systems | 319 |
| 13.5.4 | Lighting | 321 |
| 13.6 | Electronic Safety and Security Systems..... | 321 |
| 13.6.1 | Introduction | 321 |
| 13.6.2 | Cabling Infrastructure | 321 |
| 13.7 | Wireless Systems | 321 |
| 14 | Telecommunications Cabling, Infrastructure, Pathways and Spaces..... | 323 |
| 14.1 | Introduction | 323 |
| 14.2 | Telecommunications Cabling Infrastructure Classes | 323 |
| 14.2.1 | Introduction | 323 |
| 14.2.2 | Class C0 and C1 Telecommunications Infrastructure..... | 324 |
| 14.2.3 | Class C2 Telecommunications Infrastructure | 324 |
| 14.2.4 | Class C3 Telecommunications Infrastructure | 327 |
| 14.2.5 | Class C4 Telecommunications Infrastructure..... | 329 |
| 14.3 | Cabling Topology | 331 |
| 14.3.1 | Introduction | 331 |
| 14.3.2 | Horizontal Cabling Topology | 331 |
| 14.3.3 | Backbone Cabling Topology | 331 |
| 14.3.4 | Accommodation of Non-Star Configurations..... | 331 |
| 14.3.5 | Redundant Cabling Topologies | 331 |
| 14.3.6 | Low Latency Topology | 333 |
| 14.4 | Data Center Spaces for Telecommunications | 333 |
| 14.4.1 | Introduction | 333 |
| 14.4.2 | Design and Structural Requirements | 334 |
| 14.4.3 | Entrance Rooms..... | 334 |
| 14.4.4 | Main Distribution Area (MDA)..... | 335 |
| 14.4.5 | Intermediate Distribution Area (IDA) | 336 |
| 14.4.6 | Horizontal Distribution Area (HDA)..... | 336 |
| 14.4.7 | Zone Distribution Area (ZDA)..... | 336 |
| 14.4.8 | Equipment Distribution Area (EDA)..... | 336 |
| 14.5 | Outside Plant Cabling Infrastructure | 337 |
| 14.5.1 | Underground Service Pathways..... | 337 |
| 14.5.2 | Aerial Service Pathways | 337 |

| | | |
|--------------|--|------------|
| 14.6 | Access Providers | 338 |
| 14.6.1 | Access Provider Coordination | 338 |
| 14.6.2 | Redundancy | 339 |
| 14.6.3 | Access Provider Demarcation..... | 339 |
| 14.7 | Telecommunications Cabling Pathways | 343 |
| 14.7.1 | General..... | 343 |
| 14.7.2 | Security | 344 |
| 14.7.3 | Separation of Power and Telecommunications Cabling | 344 |
| 14.7.4 | Cable Tray Support Systems..... | 345 |
| 14.8 | Backbone Cabling..... | 347 |
| 14.8.1 | Introduction..... | 347 |
| 14.8.2 | General Requirements..... | 347 |
| 14.8.3 | General Recommendations | 347 |
| 14.8.4 | Cabling Types..... | 347 |
| 14.8.5 | Redundant Backbone Cabling..... | 348 |
| 14.8.6 | Backbone Cabling Length Limitations | 348 |
| 14.8.7 | Centralized Optical Fiber Cabling | 349 |
| 14.9 | Horizontal Cabling | 350 |
| 14.9.1 | Introduction..... | 350 |
| 14.9.2 | Zone Outlets, Consolidation Points, and Local Distribution Points..... | 350 |
| 14.9.3 | Redundant Horizontal Cabling..... | 351 |
| 14.9.4 | Balanced Twisted-Pair Cabling | 351 |
| 14.9.5 | Optical Fiber Cabling..... | 351 |
| 14.9.6 | Horizontal Cabling Length Limitations | 354 |
| 14.9.7 | Shared Sheath Guidelines | 354 |
| 14.10 | Cabling Installation | 355 |
| 14.10.1 | General Requirements..... | 355 |
| 14.10.2 | Cable Management | 355 |
| 14.10.3 | Bend Radius and Pulling Tension Guidelines..... | 357 |
| 14.10.4 | Abandoned Cable..... | 358 |
| 14.10.5 | Cleaning of Optical Fiber Connectors | 358 |
| 14.11 | Field Testing Data Center Telecommunications Cabling | 361 |
| 14.11.1 | Introduction..... | 361 |
| 14.11.2 | Installation Conformance..... | 362 |
| 14.11.3 | 100-ohm Balanced Twisted-Pair Cabling Field Testing | 362 |
| 14.11.4 | Optical Fiber Cabling Field Testing..... | 365 |
| 14.12 | Telecommunications and Computer Cabinets and Racks | 370 |
| 14.12.1 | Introduction..... | 370 |
| 14.12.2 | Requirements and Recommendations | 370 |
| 14.12.3 | Cabinet and Rack Configurations | 371 |
| 14.12.4 | Cabinet Airflow and Cabling Capacity..... | 373 |
| 14.12.5 | Cabinet and Rack Installations..... | 379 |
| 14.12.6 | Thermal Management in Cabinets | 384 |
| 14.13 | Telecommunications Cabling, Pathways, and Spaces Administration | 386 |
| 14.13.1 | General..... | 386 |
| 14.13.2 | Identification Conventions for Data Center Components | 387 |
| 14.13.3 | Records | 389 |
| 14.13.4 | Automated Infrastructure Management | 390 |
| 15 | Information Technology | 393 |
| 15.1 | Network Infrastructure Reliability | 393 |
| 15.1.1 | Overview..... | 393 |
| 15.1.2 | Network Infrastructure Availability Classes | 393 |

| | | |
|-------------|--|------------|
| 15.2 | Computer Room Layout | 399 |
| 15.2.1 | Introduction | 399 |
| 15.2.2 | Equipment Configuration for Efficiency | 399 |
| 15.2.3 | Connectivity Panel Distribution | 399 |
| 15.2.4 | Switch Placement | 401 |
| 15.2.5 | Material Storage | 403 |
| 15.3 | Operations Center | 404 |
| 15.3.1 | Monitoring of Building Systems | 404 |
| 15.3.2 | Location | 404 |
| 15.3.3 | Channel and Console Cabling | 404 |
| 15.3.4 | KVM Switches | 406 |
| 15.4 | Communications for Network Personnel | 406 |
| 15.4.1 | Wired/Wireless/Hands-Free Voice Communications | 406 |
| 15.4.2 | Wireless Network for Portable Maintenance Equipment | 408 |
| 15.4.3 | Zone Paging | 408 |
| 15.5 | Network Security for Facility and IT Networks | 408 |
| 15.5.1 | Overview | 408 |
| 15.5.2 | Requirements | 409 |
| 15.5.3 | Recommendations | 410 |
| 15.6 | Disaster Recovery | 410 |
| 15.6.1 | Introduction | 410 |
| 15.6.2 | Onsite Data Center Redundancy | 410 |
| 15.6.3 | Offsite Data Storage | 410 |
| 15.6.4 | Colocation Facility | 411 |
| 15.6.5 | Mirroring and Latency | 411 |
| 15.6.6 | Data Center System Failures | 412 |
| 16 | Commissioning | 413 |
| 16.1 | General | 413 |
| 16.1.1 | Introduction | 413 |
| 16.2 | Terminology | 413 |
| 16.3 | Types of Commissioning | 415 |
| 16.3.1 | New Building | 415 |
| 16.3.2 | Existing Building | 415 |
| 16.4 | Personnel and Responsibilities | 416 |
| 16.4.1 | Project Owner | 416 |
| 16.4.2 | Design Team (DT) | 416 |
| 16.4.3 | Commissioning Agent | 416 |
| 16.4.4 | Contractor and Subcontractor | 418 |
| 16.4.5 | Operation and Maintenance Staff (O&M) | 418 |
| 16.5 | Phases of the Commissioning Process | 418 |
| 16.5.1 | Overview | 418 |
| 16.5.2 | Program Phase | 419 |
| 16.5.3 | Design Phase | 420 |
| 16.5.4 | Construction & Acceptance Phase | 421 |
| 16.5.5 | Occupancy and Operations Phase | 422 |
| 16.6 | Commissioning Documents | 423 |
| 16.6.1 | Introduction | 423 |
| 16.6.2 | Owner Project Requirements (OPRs) | 425 |
| 16.6.3 | Feasibility Commissioning Study | 426 |
| 16.6.4 | Project Schedule | 426 |
| 16.6.5 | Commissioning Plan | 426 |
| 16.6.6 | Incident Registration Log | 427 |
| 16.6.7 | Basis of Design (BoD) | 427 |

| | | |
|-------------|---|------------|
| 16.6.8 | Comments on Design Reviews..... | 427 |
| 16.6.9 | Construction Specifications for Commissioning..... | 428 |
| 16.6.10 | Building Operations Manual (BOM)..... | 428 |
| 16.6.11 | Guidelines for O&M Training According to Specifications..... | 428 |
| 16.6.12 | List of Test Equipment and Functional Checklist..... | 428 |
| 16.6.13 | Compliance Technical Data Sheets (Submittals)..... | 428 |
| 16.6.14 | O&M Manual Operation and Maintenance of Systems..... | 429 |
| 16.6.15 | List of Equipment..... | 429 |
| 16.6.16 | Coordination of Systems Building Plans..... | 429 |
| 16.6.17 | Test Procedures..... | 429 |
| 16.6.18 | Agendas and Minutes of Commissioning Meetings..... | 430 |
| 16.6.19 | Training Plan..... | 430 |
| 16.6.20 | Maintenance Plan..... | 430 |
| 16.6.21 | Seasonal Testing Procedures..... | 430 |
| 16.6.22 | Commissioning Process Report..... | 430 |
| 16.6.23 | Continuous Commissioning Plan..... | 431 |
| 16.7 | Testing..... | 431 |
| 16.7.1 | Introduction..... | 431 |
| 16.7.2 | Functional Testing Components..... | 431 |
| 16.7.3 | Functional Testing Procedures..... | 431 |
| 16.7.4 | Testing Equipment..... | 431 |
| 16.7.5 | System Testing..... | 432 |
| 16.7.6 | Acceptance Testing..... | 432 |
| 16.7.7 | Electrical System Testing Example..... | 433 |
| 16.8 | System Training for Client Staff..... | 433 |
| 16.8.1 | Overview..... | 433 |
| 16.8.2 | Training Schedules..... | 434 |
| 16.8.3 | Position or Task Training..... | 434 |
| 17 | Data Center Maintenance..... | 437 |
| 17.1 | Introduction..... | 437 |
| 17.2 | Maintenance Plans..... | 437 |
| 17.2.1 | Introduction..... | 437 |
| 17.2.2 | Maintenance Philosophies..... | 437 |
| 17.2.3 | Recommendations..... | 438 |
| 17.2.4 | Additional Information..... | 439 |
| 17.3 | System Maintenance..... | 439 |
| 17.3.1 | General Requirements and Recommendations..... | 439 |
| 17.3.2 | Electrical Systems Maintenance..... | 439 |
| 17.3.3 | HVAC and Mechanical Systems Maintenance..... | 440 |
| 17.3.4 | Telecommunication Cabling and Infrastructure Maintenance..... | 441 |
| 17.3.5 | IT Equipment and Systems Maintenance..... | 441 |
| 17.3.6 | Data Center and Building System Maintenance..... | 442 |
| 17.4 | Maintenance Recordkeeping..... | 442 |
| 17.4.1 | Recommendations..... | 442 |
| 17.5 | Service Contracts..... | 443 |
| 17.5.1 | Recommendations..... | 443 |
| 17.5.2 | Example ESS Service Contract Provisions..... | 443 |

| | | |
|-------------------|---|------------|
| Appendix A | Design Process (Informative) | 445 |
| A.1 | Introduction | 445 |
| A.2 | Project Delivery Methods | 447 |
| A.3 | Facility Design Phases | 448 |
| A.4 | Technology Design Phases | 450 |
| A.5 | Commissioning | 451 |
| A.6 | Data Center Documentation | 451 |
| A.7 | Existing Facility Assessments | 452 |
| Appendix B | Reliability and Availability (Informative) | 453 |
| B.1 | Introduction | 453 |
| B.2 | Creating Mission-Critical Data Centers Overview | 454 |
| B.3 | Risk Analysis..... | 455 |
| B.4 | Availability | 455 |
| B.5 | Determining the Data Center Availability Class | 456 |
| B.6 | Data Center Availability Classes..... | 459 |
| B.7 | Availability Class Sub Groups | 462 |
| B.8 | Reliability Aspects of Availability Planning..... | 463 |
| B.9 | Other Factors..... | 464 |
| B.10 | Other Reliability Alternatives | 465 |
| B.11 | Reliability Planning Worksheet | 465 |
| Appendix C | Alignment of Data Center Services Reliability with Application and System Architecture (Informative) | 469 |
| C.1 | Overview | 469 |
| C.2 | Application Reliability | 469 |
| C.3 | Data Processing and Storage Systems Reliability..... | 473 |
| Appendix D | Data Center Services Outsourcing Models (Informative) | 477 |
| D.1 | Data Center Services Outsourcing Models | 477 |
| D.2 | Data Center Services Outsourcing Model Comparison | 477 |
| D.3 | Public Cloud Services..... | 478 |
| D.4 | Outsourcing Model Decision Tree | 479 |
| Appendix E | Multi-Data Center Architecture (Informative) | 481 |
| E.1 | Overview | 481 |
| E.2 | High Availability In-House Multi-Data Center Architecture Example..... | 482 |
| E.3 | Private Cloud Multi-Data Center Architecture Examples | 483 |
| Appendix F | Examples of Testing Documentation (Informative) | 485 |
| F.1 | Introduction | 485 |
| F.2 | Example of PDU Testing..... | 485 |
| F.3 | Example of UPS and Diesel Generator Testing | 489 |
| Appendix G | Design for Energy Efficiency (Informative) | 503 |
| G.1 | Introduction | 503 |
| G.2 | Design for Efficiency | 504 |
| G.3 | Efficiency Content of BICSI 002-2019..... | 505 |

| | | |
|-------------------|---|------------|
| Appendix H | Colocation Technical Planning (Informative) | 507 |
| H.1 | Introduction | 507 |
| H.2 | Administrative | 507 |
| H.3 | Floor Plan | 507 |
| H.4 | Ceiling Height | 507 |
| H.5 | Movement of Equipment..... | 508 |
| H.6 | Floor Loading..... | 508 |
| H.7 | Cabinets | 508 |
| H.8 | Meet-Me Rooms (MMRs) / Point-of-Presence Rooms (POPs) | 509 |
| H.9 | Cabling to MMR/POP Rooms | 509 |
| H.10 | Cabling within Cage/Suite | 510 |
| H.11 | Power | 510 |
| H.12 | Physical Security..... | 510 |
| H.13 | Storage and Staging..... | 511 |
| H.14 | Loading Dock | 511 |
| H.15 | Work Rules and Procedures | 511 |
| Appendix I | Related Documents (Informative) | 513 |

INDEX OF FIGURES

| | | |
|------------------|---|-----|
| Section 5 | Site Selection | |
| Figure 5-1 | Example of a Global Seismic Hazard Map | 31 |
| Figure 5-2 | Example of a Global Volcano Hazard Map | 32 |
| Figure 5-3 | Example of a Volcano Hazard Map | 32 |
| Figure 5-4 | Example of a Global Flooding Hazard Chart | 33 |
| Figure 5-5 | Example of a Global Tornado Risk Area Map | 34 |
| Figure 5-6 | Example of a Lightning Flash Data Map | 35 |
| Figure 5-7 | Example of a Ground Permeability Chart | 36 |
| Figure 5-8 | Example of Radial and Flight Path Zones for an Airport..... | 39 |
| Figure 5-9 | AC Electricity Distribution from Generation Stations to Data Centers..... | 41 |
| Section 6 | Space Planning | |
| Figure 6-1 | Example Module Size Decision Tree | 51 |
| Figure 6-2 | Space Adjacencies of a Traditional Data Center | 60 |
| Figure 6-3 | Space Adjacencies of Modular or Containerized Data Centers..... | 61 |
| Figure 6-4 | Examples of an OCP Open Rack (Top View & Oblique)..... | 70 |
| Figure 6-5 | Example of Aisle Width with Different Cabinet Sizes..... | 73 |
| Section 9 | Electrical Systems | |
| Figure 9-1 | Class F0 Electrical Concept Diagram (Configuration Without Backup/Alternate Power) | 105 |
| Figure 9-2 | Class F1 Electrical Concept Diagram | 106 |
| Figure 9-3 | Class F2 Concept Diagram..... | 107 |
| Figure 9-4 | Class F3 Single Utility Source with Two Utility Inputs..... | 109 |
| Figure 9-5 | Class F3 Single Utility Source with Single Utility Input | 110 |
| Figure 9-6 | Class F3 Electrical Topology (xN Or Distributed Redundant) | 111 |
| Figure 9-7 | Class F4 Electrical Topology (System-Plus-System)..... | 113 |
| Figure 9-8 | Class F4 Electrical Topology (xN Or Distributed Redundant) | 114 |
| Figure 9-9 | Class F3 Single Utility Source with Two Utility Inputs “Catcher” System | 116 |
| Figure 9-10 | Class F4 2(N+1) Electrical Topology with Dual Utility Inputs | 117 |
| Figure 9-11 | Example ATS Sizes..... | 122 |
| Figure 9-12 | Single-Module UPS with Internal Static Bypass and Maintenance Bypass from the Same Source..... | 125 |
| Figure 9-13 | Single-Module UPS with Inputs to Rectifier, Static Bypass, and Maintenance Bypass from the Same Source..... | 126 |
| Figure 9-14 | Multiple-Module UPS with Inputs to Rectifier and Maintenance Bypass from Same Source – Centralized Static Bypass..... | 127 |
| Figure 9-15 | Multiple-Module UPS with Inputs to Rectifier and Maintenance Bypass from Same Source – Paralleled Installation..... | 128 |
| Figure 9-16 | Single-Module UPS Bypass – Alternate Bypass Source - Input to Rectifier from Primary Source; Inputs to Static Bypass and Maintenance Bypass from a Second Source | 129 |
| Figure 9-17 | Multiple-Module UPS Bypass – Alternate Bypass Sources - Inputs to Rectifiers from Primary Source; Inputs to Static Bypass and Maintenance Bypass from a Second Source | 129 |
| Figure 9-18 | Single-Module UPS Bypass – Multiple Bypass Sources - Inputs to Rectifier and Static Bypass from Primary Source and Input to Maintenance Bypass from a Second Source | 130 |

| | | |
|-------------|--|-----|
| Figure 9-19 | Multiple-Module UPS Bypass – Multiple Bypass Sources - Inputs to Rectifiers and Static Bypass from Primary Source, and Input to Maintenance Bypass from a Second Source..... | 131 |
| Figure 9-20 | Topology Inside an UPS Unit..... | 131 |
| Figure 9-21 | An Example of an Approach to UPS Output Switchboard Load Management..... | 135 |
| Figure 9-22 | PDU Configuration: Single-Corded and Poly-Corded Devices..... | 136 |
| Figure 9-23 | Example of a Power Strip for Mounting in ITE Cabinets | 137 |
| Figure 9-24 | Automatic Static Transfer Switches | 138 |
| Figure 9-25 | System Capacities at Various Stages of the Electrical Distribution System..... | 145 |
| Figure 9-26 | Class F0 and F1 Circuit Mapping | 146 |
| Figure 9-27 | Class F2 Circuit Mapping | 147 |
| Figure 9-28 | Class F3 Circuit Mapping (Manual Operations)..... | 149 |
| Figure 9-29 | Class F3 Circuit Mapping (Automated Operations) | 150 |
| Figure 9-30 | Class F4 Circuit Mapping | 151 |
| Figure 9-31 | Class F3 50 to 600 V _{DC} Circuit Mapping | 152 |
| Figure 9-32 | Class F4 50 to 600 V _{DC} Circuit Mapping | 152 |
| Figure 9-33 | Example Organization of an EPO System..... | 154 |
| Figure 9-34 | Sample Power Circuits for a Class F3 Mechanical System..... | 156 |
| Figure 9-35 | Sample Power Circuits for a Class F4 Mechanical System..... | 156 |
| Figure 9-36 | Example Critical Facility Bonding and Grounding Diagram for Class F2 and Lower..... | 179 |
| Figure 9-37 | Example of Critical Facility Bonding and Grounding Diagram for Class F3..... | 180 |
| Figure 9-38 | Example Class F4 Bonding and Grounding Diagram (Two MGB and Two Entrance Facilities)..... | 181 |
| Figure 9-39 | Typical Data Center Grounding Schema (shown with raised floor)..... | 187 |
| Figure 9-40 | Typical Configuration of Flat Strip-Type SBG Within a Mesh-BN..... | 189 |
| Figure 9-41 | Adjacent Rolls Of Flat-Strip-Type SBG Being Exothermically-Welded Together..... | 189 |
| Figure 9-42 | Data Center Grounding Infrastructure (Room Level) Example | 190 |
| Figure 9-43 | Example of Equipment Rack Bonding to a Mesh-BN..... | 191 |
| Figure 9-44 | Examples of Inappropriate Equipment Rack Bonding to a Mesh-BN..... | 192 |
| Figure 9-45 | Examples of a Rack Bonding Conductor and Rack Grounding Busbar Mounting..... | 193 |
| Figure 9-46 | Example of Bonding of Cabinet Side Panel and Door | 194 |
| Figure 9-47 | Telecommunications Bonding and Grounding Infrastructure | 196 |
| Figure 9-48 | Similarity of Recommended Grounding for AC and DC Power Systems and Load Equipment.. | 197 |
| Figure 9-49 | DC Power System Showing a Single-Point Grounded Return | 198 |
| Figure 9-50 | Information Technology Equipment Showing Grounding of DC Power Input (Return Is Insulated)..... | 198 |
| Figure 9-51 | Common Bonding Network | 199 |
| Figure 9-52 | Isolated (Insulated) Bonding Network..... | 199 |
| Figure 9-53 | Sample Equipment Nameplate | 201 |
| Figure 9-54 | Example Arc Flash Warning Label (United States) | 201 |

| | | |
|-------------------|--|-----|
| Section 10 | Mechanical Systems | |
| Figure 10-1 | Chiller with Evaporative Condenser Heat Rejection System | 225 |
| Figure 10-2 | Air-Cooled Condenser Heat Rejection System | 226 |
| Figure 10-3 | Air-Cooled Chiller Heat Rejection System | 227 |
| Figure 10-4 | Evaporative Condenser Heat Rejection System | 228 |
| Figure 10-5 | Natural Water Heat Rejection System..... | 229 |
| Figure 10-6 | Computer Room Air Handler Cooling System | 230 |
| Figure 10-7 | Close Coupled Cooling System..... | 231 |
| Figure 10-8 | Liquid Cooling ITE Cooling System..... | 232 |
| Figure 10-9 | Row Integrated Cooling Systems | 233 |
| Figure 10-10 | Direct Expansion Computer Room Air Handler Cooling System..... | 235 |
| Figure 10-11 | Direct Expansion Integrated Cooling System | 236 |
| Figure 10-12 | Direct Expansion Closed Cabinet Cooling System | 237 |
| Figure 10-13 | Direct Air-Side Economizer..... | 239 |
| Figure 10-14 | Indirect Air-Side Economizer | 240 |
| Figure 10-15 | Class F0 and F1 Chiller System Example | 242 |
| Figure 10-16 | Class F0 and F1 Direct Expansion System Example | 243 |
| Figure 10-17 | Class F2 Chiller System Example | 244 |
| Figure 10-18 | Class F2 Direct Expansion System Example | 245 |
| Figure 10-19 | Class F3 Chiller System Example | 246 |
| Figure 10-20 | Class F3 Direct Expansion System Example | 247 |
| Figure 10-21 | Class F4 Chiller System Example | 248 |
| Figure 10-22 | Class F4 Direct Expansion System Example | 249 |
| Figure 10-23 | Valve Configuration Example for Pumps in Class F4 System (Shown in Figure 10-21) | 249 |
| Figure 10-24 | Class F3 Piping and Valve Redundancy Example | 250 |
| Figure 10-25 | Class F4 Piping and Valve Redundancy Example | 251 |
| Section 11 | Fire Protection | |
| Figure 11-1 | Variations of Air Flow in a Data Center with Aisle Containment | 268 |
| Figure 11-2 | Basic Fire Alarm System..... | 275 |
| Section 12 | Security | |
| Figure 12-1 | Security Measures | 277 |
| Figure 12-2 | Security Layers..... | 278 |
| Figure 12-3 | Levels of Access Control | 298 |
| Figure 12-4 | Example of an Access Control System Topology | 303 |
| Section 13 | Facility, Ancillary and IP-enabled Systems | |
| Figure 13-1 | Example DCIM Architecture | 318 |

| | | |
|-------------------|--|-----|
| Section 14 | Telecommunications Cabling, Infrastructure, Pathways and Spaces | |
| Figure 14-1 | Class C0 and C1 Concept Diagram | 325 |
| Figure 14-2 | Class C2 Concept Diagram | 326 |
| Figure 14-3 | Class C3 Concept Diagram | 328 |
| Figure 14-4 | Class C4 Concept Diagram | 330 |
| Figure 14-5 | Data Center Cabling Topology Example..... | 332 |
| Figure 14-6 | Example of a Fabric Architecture with Redundancy..... | 333 |
| Figure 14-7 | Cross-Connection Circuits to IDC Connecting Hardware Cabled to Modular Jacks in the T568A 8-Pin Sequence..... | 340 |
| Figure 14-8 | Cross-Connection Circuits to IDC Connecting Hardware Cabled to Modular Jacks in the T568B 8-Pin Sequence..... | 340 |
| Figure 14-9 | Centralized Optical Fiber Cabling Example..... | 349 |
| Figure 14-10 | Permanent Link Example | 363 |
| Figure 14-11 | Channel Model Example | 363 |
| Figure 14-12 | Blanking Panels Installed in Empty RUs..... | 373 |
| Figure 14-13 | Cabinet Aperture Opening..... | 374 |
| Figure 14-14 | Illustration of Components for Cable Capacity Formulae..... | 376 |
| Figure 14-15 | Cabinets Are Identified and Labeled..... | 379 |
| Figure 14-16 | Example of Labeled Termination Ports and Equipment Cords | 381 |
| Figure 14-17 | Effect Of Internal Hot Air Recirculation | 382 |
| Figure 14-18 | How Reducing Internal Hot Air Recirculation Reduces Input Air Temperature..... | 382 |
| Figure 14-19 | Gasket Seals Off Access Floor Tile Cutout In Vertical Cable Manager..... | 382 |
| Figure 14-20 | Brush Grommet Seals Access Floor Tile Cutout..... | 382 |
| Figure 14-21 | Illustration of Securing Cabinets and Racks on an Access Floor to a Concrete Slab Using Threaded Rod and Steel Channel | 384 |
| Figure 14-22 | Hot Aisle/Cold Aisle Cabinet Layout..... | 385 |
| Figure 14-23 | Room Grid Coordinate System Example | 387 |
| Figure 14-24 | Automated Infrastructure Management Interconnection Configuration Example..... | 391 |
| Figure 14-25 | Automated Infrastructure Management Cross-Connection Configuration Example..... | 391 |
| Section 15 | Information Technology | |
| Figure 15-1 | Class N0 and N1 Network Infrastructure | 394 |
| Figure 15-2 | Class N2 Network Infrastructure | 395 |
| Figure 15-3 | Class N3 Network Infrastructure | 397 |
| Figure 15-4 | Class N4 Network Infrastructure | 398 |
| Figure 15-5 | Simple Connection Topology..... | 400 |
| Figure 15-6 | Sample Zone Distribution Topology | 400 |
| Figure 15-7 | Sample Redundant Topology | 401 |
| Figure 15-8 | Centralized Switch Schematic | 402 |
| Figure 15-9 | End-of-Row Switch Schematic | 402 |
| Figure 15-10 | Top-of-Rack Switch Schematic..... | 403 |
| Figure 15-11 | No Radio Zone Around Suppression Tank Room..... | 407 |
| Figure 15-12 | Example of Facility & IT Network Topology | 409 |

| | | |
|-------------------|---|-----|
| Section 16 | Commissioning | |
| Figure 16-1 | General Commissioning Phases Flow Chart | 419 |
| Figure 16-2 | Pre-Design Commissioning Phase Flow Chart | 420 |
| Figure 16-3 | Design Commissioning Phase Flow Chart | 421 |
| Figure 16-4 | Construction Commissioning Phase Flow Chart | 422 |
| Figure 16-5 | Occupancy and Operations Commissioning Phase Flow Chart | 423 |
| Appendix A | Design Process (Informative) | |
| Figure A-1 | Traditional A/E Design Process | 445 |
| Figure A-2 | Data Center A/E Design Process | 446 |
| Appendix B | Reliability and Availability (Informative) | |
| Figure B-1 | Planning Process for a Mission-Critical Facility | 454 |
| Figure B-2 | Relationship of Factors in Data Center Services Availability Class | 457 |
| Figure B-3 | Sample Reliability Calculation | 463 |
| Figure B-4 | Continuous Improvement Cycle | 464 |
| Appendix C | Alignment of Data Center Services Reliability with Application and System Architecture (Informative) | |
| Figure C-1 | Class A0 and A1 Application Architecture | 470 |
| Figure C-2 | Class A2 Application Architecture | 471 |
| Figure C-3 | Class A3 and A4 Application Architecture | 472 |
| Figure C-4 | Class S0 and S1 Systems Architecture | 474 |
| Figure C-5 | Class S2 Systems Architecture | 474 |
| Figure C-6 | Class S3 Systems Architecture | 475 |
| Figure C-7 | Class S4 Systems Architecture | 476 |
| Appendix D | Data Center Services Outsourcing Models (Informative) | |
| Figure D-1 | Outsourcing Model Matrix | 478 |
| Figure D-2 | Outsourcing Decision Tree | 480 |
| Appendix E | Multi-Data Center Architecture (Informative) | |
| Figure E-1 | Reliability Framework Across All Service Layers | 481 |
| Figure E-2 | Multi-Data Center Class 3 Example | 482 |
| Figure E-3 | Multi-Data Center Class 3 Example With Three Class 2 Facilities | 483 |
| Figure E-4 | Multi-Data Center Class 4 Example with Four Class 2 Facilities | 484 |
| Appendix G | Design for Energy Efficiency (Informative) | |
| Figure G-1 | Example of Data Center Electricity Utilization | 503 |

This page intentionally left blank

INDEX OF TABLES

| | | |
|-------------------|---|-----|
| Section 5 | Site Selection | |
| Table 5-1 | Recommended Distances from Man-Made Elements | 38 |
| Table 5-2 | Utility Reliability Examples | 43 |
| Table 5-3 | Recommended On-Site Supply of Services for Data Center Facility Classes | 46 |
| Section 6 | Space Planning | |
| Table 6-1 | Example of a Module Size Design Checklist | 52 |
| Table 6-2 | Liquid and Air-Cooled System Options and Primary Design Parameters | 58 |
| Table 6-3 | Data Center Energy Saving Opportunities | 80 |
| Section 7 | Architectural | |
| Table 7-1 | Minimum Fire Rating of Spaces | 91 |
| Table 7-2 | Computer Room Access Floor Performance Specifications | 93 |
| Table 7-3 | Suspended Ceiling Infrastructure Mounting Recommendations | 95 |
| Section 9 | Electrical Systems | |
| Table 9-1 | Design Efficiency Ratios | 103 |
| Table 9-2 | Class F0 Electrical System Overview | 105 |
| Table 9-3 | Class F1 Electrical System Overview | 106 |
| Table 9-4 | Class F2 Electrical System Overview | 107 |
| Table 9-5 | Class F3 Electrical System Overview | 108 |
| Table 9-6 | Class F4 Electrical System Overview | 112 |
| Table 9-7 | Low-Voltage Distribution Voltages in Some Major Data Center Locations | 119 |
| Table 9-8 | Static Bypass Switch Input, By Availability Class | 132 |
| Table 9-9 | Summary of UPS Output Switchboard Counts for Classes | 133 |
| Table 9-10 | Transformer Wirings and Output Voltages Commonly Used in Data Centers | 136 |
| Table 9-11 | Multipliers for Electrical Distribution System Components | 144 |
| Table 9-12 | Types and Applications of Li-ion Batteries | 168 |
| Table 9-13 | Battery Standards Cross-Reference Table (IEEE Standard Number) | 169 |
| Table 9-14 | Class Requirements for Temperature Sensors | 174 |
| Table 9-15 | SPD Locations as per Class | 184 |
| Table 9-16 | Grounding and Bonding Connection Schedule | 190 |
| Table 9-17 | Electrical Systems Availability Classes | 203 |
| Section 10 | Mechanical Systems | |
| Table 10-1 | Section 10 Text References | 221 |
| Table 10-2 | Class F0 and F1 Mechanical System Overview | 241 |
| Table 10-3 | Class F2 Mechanical System Overview | 243 |
| Table 10-4 | Class F3 Mechanical System Overview | 245 |
| Table 10-5 | Class F4 Mechanical System Overview | 247 |
| Section 11 | Fire Protection | |
| Table 11-1 | Recommended Detection Systems for Data Center Spaces | 269 |
| Table 11-2 | Recommended Sprinkler Systems for Data Center Spaces | 272 |

| | | |
|-------------------|--|-----|
| Section 12 | Security | |
| Table 12-1 | Minimum Lighting Levels..... | 284 |
| Table 12-2 | Thickness of Concrete Wall for Projectile Protection | 289 |
| Table 12-3 | Vehicle Barrier Comparison..... | 290 |
| Table 12-4 | Speed Of Concrete Wall Penetration..... | 291 |
| Table 12-5 | Time to Penetrate Industrial Pedestrian Doors | 292 |
| Table 12-6 | Time to Penetrate Windows | 293 |
| Section 14 | Telecommunications Cabling, Infrastructure, Pathways and Spaces | |
| Table 14-1 | Class C0 and C1 Overview..... | 324 |
| Table 14-2 | Class C2 Overview | 324 |
| Table 14-3 | Class C3 Overview..... | 327 |
| Table 14-4 | Class C4 Overview | 329 |
| Table 14-5 | Maximum Cable Stacking Height in Cabling Pathways..... | 343 |
| Table 14-6 | Balanced Twisted-Pair Cabling Channel Performance..... | 352 |
| Table 14-7 | Optical Fiber Cable Performance By Type | 352 |
| Table 14-8 | Balanced Twisted-Pair Cable Bend Radius and Pulling Tension | 357 |
| Table 14-9 | Optical Fiber Cable Bend Radius and Pulling Tension | 358 |
| Table 14-10 | Balanced Twisted-Pair Field Testing..... | 364 |
| Table 14-11 | Reference Jumper Repeatability Allowance..... | 367 |
| Table 14-12 | Common IEEE Applications Using Multimode Optical Fiber Cabling..... | 368 |
| Table 14-13 | Common IEEE Applications Using Singlemode Optical Fiber Cabling | 368 |
| Table 14-14 | Common Fibre Channel Applications Using Optical Fiber Cabling | 369 |
| Table 14-15 | Alternative Rack Specifications | 370 |
| Table 14-16 | Example of Cabinet Depth Guidelines | 373 |
| Table 14-17 | Available Space for Calculating Cabinet Vertical Cable Capacity..... | 380 |
| Section 15 | Information Technology | |
| Table 15-1 | Tactics for Class N0 and N1 | 394 |
| Table 15-2 | Tactics for Class N2 | 395 |
| Table 15-3 | Tactics for Class N3 | 396 |
| Table 15-4 | Tactics for Class N4 | 396 |
| Table 16-1 | Commissioning Documentation Matrix | 424 |
| Appendix B | Reliability and Availability (Informative) | |
| Table B-1 | Identifying Operational Requirements: Time Available for Planned Maintenance Shutdown..... | 457 |
| Table B-2 | Identifying Operational Availability Rating: Maximum Annual Downtime (Availability %)..... | 458 |
| Table B-3 | Classifying the Impact of Downtime on the Mission | 459 |
| Table B-4 | Determining Data Center Services Availability Class..... | 459 |
| Table B-5 | Tactics for Class 0 | 460 |
| Table B-6 | Tactics for Class 1 | 460 |
| Table B-7 | Tactics for Class 2 | 461 |
| Table B-8 | Tactics for Class 3 | 461 |
| Table B-9 | Tactics for Class 4 | 462 |
| Table B-10 | Relationship Between Availability Percentage and Allowable Downtime..... | 464 |

Appendix C Alignment of Data Center Services Reliability with Application and System Architecture (Informative)

| | | |
|-----------|-----------------------------------|-----|
| Table C-1 | Tactics for Class A0 and A1 | 470 |
| Table C-2 | Tactics for Class A2 | 471 |
| Table C-3 | Tactics for Class A3 and A4 | 472 |
| Table C-4 | Tactics for Class S0 and S1 | 473 |
| Table C-5 | Tactics for Class S2..... | 474 |
| Table C-6 | Tactics for Class S3..... | 475 |
| Table C-7 | Tactics for Class S4..... | 476 |

This page intentionally left blank

PREFACE

Revision History

- June 18, 2010** First publication of this standard, titled BICSI 002-2010, *Data Center Design and Implementation Best Practices*
- March 15, 2011** Revision of BICSI 002-2010 published as ANSI/BICSI 002-2011, *Data Center Design and Implementation Best Practices*

Major revisions include:

- Addition of Section 9, *Electrical*
- Addition of Section 14, *Telecommunications*

Minor revisions include: definitions, updating of graphics for printing and readability, other editorial corrections

- December 9, 2014** Revision of ANSI/BICSI 002-2011 published as ANSI/BICSI 002-2014, *Data Center Design and Implementation Best Practices*

Major revisions include:

- Revision of Class F0 – F4 electrical infrastructure, including the removal of the requirement for a second power utility connection in Section 9, *Electrical*.
- Revised telecommunications Availability Classes C3 and C4 concerning the redundancy of main and horizontal distributors in Section 14, *Telecommunications*.
- Added, expanded and revised Availability Class structure to mechanical, telecommunications and network infrastructure (see Sections 9, 14, and 15 respectively).
- Addition of Appendix C, Alignment of Data Center Services Reliability with Application and System Architecture.
- Addition and revision of content for modular and containerized data centers in Section 6, *Space Planning* and Section 9, *Electrical*.
- Introduced content on DCIM and renamed Section 13 to *Data Center Management and Building Systems*.
- Expanded content regarding DC power and safety in Section 9, *Electrical*.
- Addition of hot and cold aisle containment in Section 6, *Space Planning* and Section 11, *Fire Protection*.
- Added and expanded content regarding designing for energy efficiency in multiple sections and added Appendix G, *Design for Energy Efficiency*.
- Addition of Appendix D, Data Center Services Outsourcing Models.
- Addition of Appendix E, Multi-Data Center Architecture.
- Updated cabinet door air flow and cable capacity calculations in Section 14, *Telecommunications*.

Minor revisions include:

- Moved former Section 5, *Space Planning* to directly after former Section 6, *Site Planning*.
- Restructuring of Section 5, *Site Planning*, Section 14, *Telecommunications*, and Section 16, *Commissioning*.
- Expansion of content to reflect both new and international design practices.
- Revisions to Appendix B, *Reliability and Availability*, to accommodate extension of availability classes.
- Update Section 8, *Structural*, to align with revisions to the *IBC* and related standards.

List continues on the next page

- Updated Section 10, *Mechanical*, to reflect expanded ASHRAE guidelines for temperature and humidity.
- Updated Section 11, *Fire Protection* section to reflect changes in NFPA 75 and NFPA 76.
- Updated Section 14, *Telecommunications*, to reflect updates to ISO, TIA, and CENELEC data center cabling standards including cable types (removed OM1 and OM2, recommend OM4, added Category 8) and addition of intermediate distributor.
- Revised content regarding zinc whiskers and moved to Section 7, *Architectural*.
- Added content on testing equipment, system testing, acceptance testing, equipment operations and maintenance manuals, and system training to Section 16, *Commissioning*.
- Revised and moved system availability information to Appendix B, *Reliability and Availability*. (content formerly in Section 17, *Maintenance*).
- Added new content on maintenance plans and service contracts in Section 17, *Maintenance*.
- General content relocation and editorial corrections to improve readability and reduce ambiguity.

May 1, 2019 Revision of ANSI/BICSI 002-2014 published as ANSI/BICSI 002-2019, *Data Center Design and Implementation Best Practices*

Notable content relocation to BICSI 009-2019 includes:

- Operational security topics from Section 12, *Security*
- Operational maintenance topics from Section 17, *Data Center Maintenance*

Major revisions include:

- Revision and addition of content for, and related to, equipment cabinets and racks, including open racks and Open Compute Project® infrastructure within multiple sections
- Revision of computer room requirements and recommendations in Section 6, *Space Planning*
- Expansion of electrical busway content in multiple sections
- General restructure, including an update and expansion to heat rejection and cooling system technologies in Section 10, *Mechanical Systems*
- Restructure of Section 12, *Security*
- Title change of Section 13 to *Facility, Ancillary and IP-enabled Systems*, with addition of applicable content
- Revision and expansion of Section 16, *Commissioning*
- Addition of Appendix H, *Colocation Technical Planning*

Minor revisions include:

- Additions or revisions to airports volcanoes, and microgrids in Section 5, *Site Selection*
- Revision of access control and video surveillance systems within multiple sections
- Expansion of equipment access and pathway (e.g., ramps) requirements and recommendations within Section 6, *Space Planning* and Section 7, *Architectural*
- Update to access floors requirements for seismically active areas in Section 8, *Structural*
- Addition of lithium ion (Li-ion) batter information within multiple sections
- Alignment of telecommunications bonding and grounding terminology to international usage in Section 9, *Electrical Systems*
- Revision of equipment cabinet and rack bonding in Section 9, *Electrical Systems*
- Addition of oxygen deletion systems and fire alarm systems and an update to gaseous fire suppression systems in Section 11, *Fire Protection*
- Addition of time synchronization in Section 12, *Security*
- Expansion of content related to entrance facilities, entrance rooms, and meet-me rooms in multiple sections
- Addition of ICT infrastructure requirements for supporting and non-computer room systems
- Revision to permissible backbone and horizontal cabling media and addition of optical fiber connector cleaning in Section 14, *Telecommunications Cabling, Infrastructure, Pathways and Spaces*

List continues on the next page

- Expansion of network topologies and fabrics in Section 15, *Information Technology*
- Addition of maintenance plan philosophies in Section 17, *Data Center Maintenance*
- Addition of existing facility assessments to *Appendix A, Design Process*
- General content relocation and editorial corrections to improve readability and reduce ambiguity

Document Format (Usability Features)

This standard has the following usability features as aids to the user:

- Additions and changes, other than those for editorial purposes, are indicated with a vertical rule within the left page margin.
- Deletion of one or more paragraphs is indicated with a bullet (•) between the content that remains

NOTE: The relocation of content within or between sections (e.g., Section 10, *Mechanical Systems*, Section 12, *Security*) related to structure, readability, or content alignment is not indicated.

Translation Notice

This standard may have one or more translations available as a reference for the convenience of its readers. As that act of translation may contain inconsistencies with the original text, if differences between the translation and the published English version exist, the English text shall be used as the official and authoritative version.

This page intentionally left blank

1 Introduction

1.1 General

This standard is written with the expectation that the reader is familiar with the different facets of the design process (See Appendix A). The reader should understand from which role and point of view he or she intends to use this document (e.g., information technology, facilities, other corporate internal or external to the owner). Refer to Sections 1.2.1 – 1.2.3 below.

1.2 Purpose

This standard provides a reference of common terminology and design practice. It is not intended to be used by architects and engineers as their sole reference or as a step-by-step design guide, but may be used by such persons to determine design requirements in conjunction with the data center owner, occupant, or consultant.

This standard is intended primarily for:

- Data center owners and operators
- Telecommunications and information technology (IT) consultants and project managers
- Telecommunications and IT technology installers

Additionally, individuals in the following groups are also served by this standard.

1.2.1 Users Within IT

1.2.1.1 IT and Telecommunications Designers

IT and telecommunications designers and consultants may use BICSI 002 in conjunction with the appropriate local telecommunications infrastructure standard (e.g., ANSI/TIA-942-B, AS/NZS 2834-1995 Computer Accommodation, CENELEC EN 50173 Series, ISO/IEC 24764) to design the telecommunications pathways, spaces, and cabling system for the data center. The telecommunications designer/consultant should work with the data center architects and engineers to develop the IT and telecommunications equipment floor plan using guidelines specified in this standard.

1.2.1.2 IT and Telecommunications Management

IT and telecommunications management may use BICSI 002 as an aid in defining initial data center design requirements based on required levels of security, reliability, and availability. IT and telecommunications should work with information protection management, the business continuity group, and end user departments to determine the required levels of security, reliability, and availability.

1.2.1.3 IT Operations Management

Working with facilities groups, IT operations managers may use BICSI 002 to guide the requirements they specify to outsource suppliers who provide computing services and server room IT operations.

1.2.1.4 Information Security

Information security personnel may use BICSI 002 as a guide in defining and implementing information protection and security and assisting in the development of standard policies and operating procedures.

1.2.2 Users Within Facilities Group

1.2.2.1 Technical Representatives Within Facilities Group Capital Projects

Facilities group technical representatives may use BICSI 002 as a guide during the project planning phase as they estimate costs, prepare preliminary design and construction schedules, and prepare requests for professional services (RFPS) for the design and construction of new or renovated IT facilities. Thus, after the method of project delivery is determined, BICSI 002 becomes a referenced document in the RFPS that the facilities group prepares and issues to architecture and engineering (A/E) and design-build (D/B) firms. These companies, in turn, bid on the design and construction of the IT facilities.

1.2.2.2 Facilities Management Representatives Within Facilities Group

Facilities operations and management may use BICSI 002 as a guide in planning the operation and maintenance of corporate IT facilities so that these facilities maintain defined levels of reliability and availability. For example, BICSI 002 provides guidance in defining training needs and maintenance schedules of critical equipment for operations and maintenance personnel.

1.2.3 Staff Outside IT and Facilities Groups

1.2.3.1 Physical Security Management

Security staff responsible for physical security management may use BICSI 002 as a guide in determining physical security and fire protection system requirements for IT facilities.

1.2.3.2 External Resources

1.2.3.2.1 Telecommunications Consulting Firms

BICSI 002 is useful to telecommunications consulting firms or design/build installation firms by providing guidance in the design and construction of IT facilities for the corporation.

1.2.3.2.2 A/E and Construction Firms

BICSI 002 is useful to A/E and construction firms to guide them in the process of design and construction of IT facilities. It provides a reference of common terminology and reliability topologies. It is not intended to be used by A/E and construction firms as their sole reference, and it is not meant to provide a step-by-step design guide for the A/E or D/B firms; however, it may be used by such persons to guide design requirements in conjunction with the data center owner, occupant, or consultant.

1.3 Categories of Criteria

Two categories of criteria are specified — mandatory and advisory:

- Mandatory criteria generally apply to protection, performance, administration and compatibility; they specify the absolute minimum acceptable requirements.
- Advisory or desirable criteria are presented when their attainment will enhance the general performance of the data center infrastructure in all its contemplated applications.

Mandatory requirements are designated by the word *shall*; advisory recommendations are designated by the words *should*, *may*, or *desirable*, which are used interchangeably in this standard. Where possible, requirements and recommendations were separated to aid in clarity.

Notes, cautions and warnings found in the text, tables, or figures are used for emphasis or for offering informative suggestions.

2 Scope

This standard provides best practices and implementation methods that complement TIA, CENELEC, ISO/IEC and other published data center standards and documents. It is primarily a design standard, with installation requirements and guidelines related to implementing a design. The standard includes other installation requirements and guidelines for data centers where appropriate.